# FE212 WIRE DRAG

Diagram No. 1247

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

# DESCRIPTIVE REPORT

(HYDROGRAPHIC)

Type of Survey Wire Drag

Field No. RH-20-3-73

Office No. FE-212WD

LOCALITY

State Florida

General Locality Jupiter Inlet

Locality Offshore

1973

CHIEF OF PARTY

CDR L.E. Pickens

LIBRARY & ARCHIVES

DATE November 20, 1974

NOTE: A new system for registering Field Examinations (FE's) was established in 1980. All FE's are now consecutively numbered as shown hereon. The date shown in the new format is the actual date of survey. This material was previously registered as;

FE No.1 1974WD

FESTS WRE DRAG

# FENO.1 1974 WIRE DRAG

FEDIZ

Diag. Cht. No. 1247.

FORM C&GS-504

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

# DESCRIPTIVE REPORT

Type of Survey WIRE DRAG

Field No. RH-20-3-73 Office NoSP-AMC-1-RH-73

## LOCALITY

State FLORDIA

General locality JUPITER INLET

Locality OFFSHORE

19.73

CHIEF OF PARTY

CDR.L.E.PICKENS

LIBRARY & ARCHIVES

DATE 11-20-74

WEE DRAG

FORM	C&	GS-	537
1=1			

#### U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SÉRVICES ADMINISTRATION COAST AND GEODETIC SURVEY

REGISTER NO.

## HYDROGRAPHIC TITLE SHEET


INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form,	FIELD NO.
filled in as completely as possible, when the sheet is forwarded to the Office.	RH 20-3-73
State FLORIDA	
General locality JUPITER INLET	
Locality	
Scale 1:20,000 Date of su	20-27 MARCH 1973
Instructions dated 15 JANUARY 1973 Project N	o. SP-AMC-1-R/H-73
Vessel NOAA SHIPS RUDE & HECK	
Chief of partyCDR. L.E.PICKENS	
Surveyed by SHIPS' PERSONNEL	
Soundings taken by echo sounder, hand lead, pole	
Graphic record scaled by	
Graphic record checked by	
Protracted by Autom	ated plot by CALCOM! AMC
Soundings penciled by AMC Personnel	
Soundings in Markans feet at MLW MEKW BASED O	N PREDICTED TIDES
REMARKS: Ship and Nif buoys plotted !	
_ all other work done manually	

#### TABLE OF CONTENTS


- I. SHEET LAYOUT
- PROGRESS SKETCH II.
- III. A) AUTHORITY
  - B) CHARACTER & LIMITS OF THE WORK
  - C) CONTROL & SHORELINE
  - D) DATE OF SURVEY
  - E) TIDAL REDUCERS
    F) JUNCTIONS

  - G) SPLITS
  - H) GROUNDINGS & HANGS
  - I) GENERAL NOTES
  - J) CURRENTS
  - K) DISCREPANCIES & COMPARISONS WITH RECENT SURVEYS & CHARTS
    L) PERSONNEL & EQUIPMENT
    M) MISCELLANEOUS

  - N) SUMMARY
  - O) RECOMMENDATIONS
  - P) APPROVAL
- IV. LIST OF ATTACHMENTS



OPR-SP-AMC-1-R/H-73
WIRE DRAG- SHEET 20-3-73
JUPITER INLET, FLORIDA
NOAA SHIPS RUDE & HECK
L.E.PICKENS, CHIEF OF PARTY
MARCH 1973
SCALE 1:80,000



<del>|</del> 27 00

4

PROGRESS SKETCH

#### DESCRIPTIVE REPORT

#### TO ACCOMPANY

WIRE DRAG FIELD NUMBER RH-20-3-73

PROJECT SP-AMC-1-R/H-73

JUPITER INLET, FLORIDA

1973

CDR L.E. PICKENS

#### NOAA SHIPS RUDE & HECK

#### A. AUTHORITY -

This project was authorized under Project Instructions SP-AMC-1-R/H-73, Wire Drag, Southeast Coast Investigations, dated: 15 January 1973; also, Change 1, dated 9 February 1973, Change 2, dated 14 February 1973, and Change 3, dated 22 February 1973.

#### B. CHARACTER AND LIMITS OF THE WORK -

The purpose of this project was to investigate and prove or disprove the existence of a reported item offshore of Jupiter Inlet, Florida.

The locality of the survey, covered by C&GS Charts 1247, 1248, and 1112

(book sheet)

is as follows: Sheet layout is from Latitude 26°51'N to 27°04'N and from Longitude 79°59'W to 80°08'W.

The reported position of the item is as follows: Item B-4: Latitude 27°00.6'N, Longitude 80°02.8'W. (Approx. Charled pos.

The entire survey was conducted on a scale of 1:20,000 using Raydist DR-S Range-Range control.

#### C. CONTROL AND SHORELINE

Raydist DR-S Range-Range control was utilized. The Raydist was operating on a frequency of 3300.4 KHz, giving a lane width of 45.39904 meters.

There was no shoreline on the sheet. Shareline added from chart 1247 in brown (HWL termined off)

Two Raydist shore stations, FAT and WORTH, were utilized for control.

FAT, located 6.7 miles north of the Fort Pierce, Florida entrance channel, served as the Red station. WORTH, located near Jupiter Inlet, Florida, served as the Green station.

Upon completion of the survey, the stations were dismantled, but both stations are recoverable as described in the enclosed station descriptions under attachment VII. A list of all signals used is given in Attachment I.

#### D. DATE OF SURVEY

(FE No. 1, 1974)
Operations on SP-AMC-1-R/H-73 (Sheet R/H-20-3-73) were begun on 20 March
1973 and completed on 27 March 1973.

#### E. TIDAL REDUCERS

Preliminary reduction of each days data was done using predicted tides.

Actual tidal data has been furnished by the Rockville, Office for the standard tide gauge at Miami, Beach, Florida with correctors for Fort Pierce, Florida.

Servicing and levels to this gauge were not required.

#### F. JUNCTIONS

Not applicable.

#### G. SPLITS

No splits exist on Sheet R/H-20-3-73. F = 10.1, 1974

#### H. GROUNDINGS AND HANGS

See Attachment II.

#### I. GENERAL NOTES

Norming and evening calibrations were generally made by running a range off the Fort Pierce Channel Entrance (see Attachment I).

In addition to morning and evening calibrations, frequent lane counts were taken whenever practical on navigation buows.

Throughout this survey an 800 ft. towline was utilized; thus the distance of from the Raydist antenna to the end buoy was 265 meters.

The following occurance should be noted when verifying this survey:

A Day (20 March 1973)

(according to divers)

Strip 2: Hung metal bar progruding one foot from bottom in 35 feet of water at the same time we hung buoy R "WR16". Few tests due to fact both launches broken down and weather was marginal for skiff use.

#### J. CURRENTS

In general, currents were from the North. However, it was found to be advantageous to conduct our own "current survey" prior to planning a strip. This was accomplished by setting a tester to the approximate depth of the drag, plotting its position as it entered and again as it was retrieved from the water and noting the length of time involved. In this manner both volocity and direction were determined.

K. DISCREPANCIES AND COMPARISIONS WITH RECENT SURVEYS AND CHARTS
In accord with Page 3, Paragraph 2 of Project Instructions, prominent
new landmarks were located, charted landmarks were re-evaluated, and
a letter sent to Coast Pilot Branch. See Attachment IX.

In general, charted depths from the most recent charts were found to be quite reliable, and were used daily in conjunction with hydrographic surveys supplied by AMC and Ship Hydro run immediately prior to wire dragging.

#### L. PERSONNEL AND EQUIPMENT

Throughout this survey the RUDE & HECK acted as guide and end vessel respectively. Both ships are equipped with Raytheon DE-723 fathometers which were used to plan the drag strips. Ship's launches and skiffs alternated as drag tester units, dependent on the state of the sea and the weather.

Standard wire drag equipment was used throughout the survey. It should be noted that during the 1972-73 inport pariod, some new intermediate buoys were obtained. These buoys were left over from the old drag boats - WAINWRIGHT & HILGARD. These buoys appear to be the same as our standard intermediate buoys, however, some question exists as to the weight and towing characteristics.

Officers aboard during this survey included: CDR L.E. Pickens, LCDR W.M. Noble, LTJG S.H. Manzo, LTJG B.L. Wescott, ENS H.B. Arnold, ENS R.D. Wells, and ENS T.A. Bergner.

#### M. MISCELLANEOUS

Operations were hampered by launch breakdowns and by heavy swells originating to the northeast of the working area. The latter resulted in accepting a larger combined lift and swell than normal, and thereby reducing effective depths achieved.

#### N. SUMMARY

Item B-4

this position was not covered by deep enough effective depths

(4

A wreck'at Lat. 27°00.61'N, Long, 80°02.8'W shown charted as cleared to a learned to learn

#### O. RECOMMENDATIONS

Recommend Item B-4 be charted as cleared to 25 feet. This item is considered complete.

#### APPROVAL SHEET

All record of this survey prior to smooth plotting are hereby approved.

Item B-4 is considered complete and adequate for charting. The field work was personally supervised by the undersigned and the boat sheet and records were inspected daily.

CDR Leonard E. Pickens Commanding Officer NOAA Ships RUDE & HECK

#### LIST OF ATTACHMENTS

- A) RAYDIST CONTROL STATIONS I.
  - B) VISUAL CONTROL SIGNALS
- II. LIST OF GROUNDINGS AND HANGS
- A) DAILY RAYDIST CORRECTORS III.
  - B) ELECTRONIC CALIBRATION INFORMATION
- IV. STATISTICS
- ٧. AIDS TO NAVIGATION
- PROJECT INSTRUCTIONS VI.
  - A) CHANGE #1
    B) CHANGE #2

  - C) CHANGE #3
- RAYDIST STATION DESCRIPTIONS VII.
- VIII. TIDES
- IX. COAST PILOT CHANGES
- х. PARAMETERS

  - A) BOAT SHEET, REQUEST FOR B) ELECTRONIC CONTROL PARAMETERS

#### ATTACHMENT I

Α.	RAYDIST CON	TROL STATIONS	
station	lattitude	longitude	remarks
FAT	27 34 38.629	80 19 38.080	RED STATION
WORTH	26 57 37.855	80 05 02.040	GREEN STATION
В.	VISUAL CONT	ROL SIGNALS	
signal	lattitude	longitude	remarks
PIERCE 2	27 28 11.217	80 17 27.9	FRONT RANGE
TANK	27 27 23.520	80 19 44.1	REAR RANGE
J.C. PARK . TANK	27 27 10 <b>.</b> 160	80 17 13.3	LEFT ANGLE

<sup>\*</sup> NOTE: Pierce 2 was a visual signal constructed by ship's personnel over the disc of the same name. The structure was approximately 25 feet tall.

ATTACHMENT II
LIST OF GROUNDINGS AND HANGS

Position No. & Dayletter	Buoy No.	Lattitude	Longitude	Grounded Effective Depth	Cleared by Day & Strip No.	Cleared Effective Depth	Charted Depth	Remarks
19-A	2-3		80 02.80	34 35	A-11	29	<u>81</u>	Metal bar extending one foot above bottom. Not considered a hazard
19 <b>-</b> A	2-3	27 00.58	80 02.61				31	Hung buoy "WR16" from S. to N. at same time as above hang.
10-B	5-6	27 00.58	80 02.61				31	Hung buoy "WR16" from

# ATTACHMENT

# DAILY RAYDIST CORRECTORS

		RUI	Œ	HE	CK
Date	Day letter	Red	Green	Red	Green
20 March 1973	Α	+0.2	0.0	-0.1	-0.1
27 March 1973	В	0.0	0.0	-0.1	-0.2

## ATTACHMENT IV

# STATISTICS

date	day l <b>e</b> tter	strip no.	volume no.	no. of positions	LNM	SNM
20 March 19	73 A	1	I	10	1.65	1.49
20 March 19	73 A	51	I	. 9	1.20	1.02
27 March 19	73 B	1	I	13	1.20	1.08

ATTACHMENT V
FLOATING AIDS TO NAVIGATION

name	lattitude	longitude	remarks	
BUOY "10A"	27 26.55	80 13.45	Used to check la	ane count.
Buoy R"12"	27 23.18	80 07.65	Used to check la	ane count.
Buoy R"WR12A"	27 23.45	80 03.15	Used to check la	ane count.
Keeper Buoy for R"WR12A"	27 23.43	80 03.38	Used to check la	ane count.
Buoy R"WR16"	27 00.58	80 02.62	Used to check la	ane count.

## ATLANTIC MARTHE CENTER

# ELECTRONIC CONTROL PARAMETERS

		58- AMC-1	1 - P/A -	13				- 77
	1.	Project #-OPR-		2. Reg. #	<u>H-</u>	_ 3. Fiel	d # RH-20-	3-13
	4.	Type of Contro	1 12	Aydist		(Hi-Fix,	Raydist,	EPI, etc.)
	5	Frequency 330	00.4	(for co	onversion	of electr	onic lanes	to meters)
	6.	Mode of Operat	cion (ch	eck one):				
		Range-Range	X		R	Range-Visua	1 [	
	Č	Range One Station Range, Two Station	I.D		<del></del>	Lat. 27 Long. 80 Lat. 26 Long. 80	° 19	38.629" 38.080" 37.855" 02.040"
		Hyperbolic (			H	Typer-Visua	1	
		Slave One Station Master Station				Lat. Long. Lat. Long.	0 0	1 11
		Slave Two			• ,-	Lat.		
		Station				Long.		
	7.	Location of Su						
		Range-Range	(C)			is standi R <sub>2</sub> (check	ng at R <sub>1</sub> S one):	tation and
				Survey and	rea is to	observer'	s Right	Ŋ=β
				Survey an	rea is to	observer'	s Left	A=1
		Hyperbolic		ooking fro	om survey	area towa	rd Master	Station:
				Slave One	e must be	to observ	er's Left.	
				Slave Two	o must be	e to observ	er's Right	•
-	1	This form	is subm	itted as	an aid ir	preparing	a boat sh	eet.
		This form	applies	to all d	ata on th	nis survey.		
		This form	applies	to part	of the da	nta on this	survey.	
		Vessel EDP #	Fine Time	om Day		Po Day	Position (inclu	
							t	0
	9.	Remarks: R	1R	ED.	R2.	131.U.E		

# PROJECTION PARAMETERS

# POLYCONIC OR MODIFIED TRANSVERSE MERCATOR

1. Project No. SP-AMC-1-R/H-73 4. Requested By M. W. Johnson AMC
2. Reg. No. H-9469 5. Ship or Office Verification
3. Field No. R/H 20-3-73 6. Date Required asap
7. Polyconic Modified Transverse Mercator
8. Central Meridian of Projection 080 ° 02 ' 00 "
9. Survey Scale: 1: <u>20,000</u>
10. Size of Sheet (check one):
36 x 54 36 x 60 Other xx Specify 36"x36"
11. Sheet Orientation (check one):
$NYX = 1$ $NYX = \beta x$
· N
N
CMER
12. Plotter Origin: S.W. Corner of Sheet (not necessarily a grid intersection)
Latitude 26 ° 50 ' 00 "
Longitude 080 ° 09 ' 00 "
13. G.P.'s of triangulation and/or signals attached $\lfloor x \rfloor$
14. Material Desired: Tracing Paper Mylar
Smooth Sheet x & Other x Specify A&D sheet .003 mylar
15. Remarks: Smooth sheet type grid and Raydist arcs
A&D sheet, tick marks only

# ATLANTIC MARINE CENTER APPROVAL SHEET FOR AUTOMATED SURVEY H- 3569 WD SP-AMC-I-RH-73

A. All revisions and additions made on the smooth sheet during verification have been entered in the magnetic tape records for this survey. A new final position printout has/has not been made. A new final sounding printout has/has not been made. NA

Date: November 14,1974

Signed:

wellong Joms

Title:

Chief, Verification Branch

B. The verified smooth sheet has been inspected, is complete, and meets the requirements of the Hydrographic and AMC Manuals. Exceptions are listed in the verifier's report.

Date: November 14.1974

Signed:

C. Oak north J.

Title:

C.Dale North, Jr. LCDR, NOAA Chief, Processing Division

### VERIFICATION NOTES SURVEY H-SP-AMC-1-RH-73 RH-20-3-73

This wire drag survey appears to be complete. The location and clearence of the wreck, item B4, appears to be adequate.

Norfolk, Va. November 11.1974 William L.Jonns Chief, Verification Branch, AMC.

Name on Survey	NOAA FORM 76-155 (11-72)	NA	TIONAL O	CEANIC	U.S. DE	PARTME	NT OF	COMMERCE		JRVEY N	UMBER	
2 2 3 3 3 4 4 4 5 5 5 5 5 6 6 6 6 6 6 6 6 6 6 6 6		GEO	GRAPH						F.I	E.No. I W.D.	L <del>-</del> 1974	
2 2 3 3 3 4 4 4 5 5 5 5 5 6 6 6 6 6 6 6 6 6 6 6 6	Name on Survey		0'	CHART NO.	PREVIOUS SI	JAVET ON PS	DA CAMPORM	TION ME	P.O. GUIDE	OR MAP	J.S. LIGHT V	s <sup>1</sup>
3 3 4 4 5 5 5 5 6 6 6 6 7 7 7 7 7 8 8 8 8 9 9 9 9 9 10 10 10 10 10 10 10 10 10 10 10 10 10			<u> </u>				<u> </u>					1
4												2
5												3
6											ļ	4
												5
												6
9		١										7
					<u> </u>							8
							<u> </u>					9
12 13 14 14 15 16 17 18 18 19 20 21 21 22					-							10
13 14 14 15 16 17 18 18 19 19 20 21 21 22							-					11
											-	12
				-			-					13
						ļ			-			+
17 18 19 20 21 21 22 23			<u> </u>	-		-				-		+
18 19 20 21 21 22 23			-	<del> </del>	-	-						+
19 19 20 20 21 21 22 23 23 24	:				-	-	-				-	
20 20 21 22 22 23 24		:			-	1.	-					
21 22 22 23 24				-			-					+
22 23 24			-						-			
23							-					
24							-					_
			-		-	-			+			_
			<del> </del>				<del> </del>					25

NOAA FORM 77-27 (9-72) (PRESC. BY HYDROGRAPHIC MANUAL 20-2, 6-94, 7-13)

# HYDROGRAPHIC SURVEY STATISTICS HYDROGRAPHIC SURVEY NO. \_\_\_\_\_\_F.E.No.1-1974 W.D.

RECORDS ACCOMPANYING SURVEY: To be completed when survey is registered.

RECOR	DESCRIPTION		AMO	TNUC	RECORD DESCRIPTION			AMOUNT
SMOOTH SHEET				1	Wire BOATS	drag stri	ips	6
DESCRIPTIVE RE	PORT			1	OVERL	AYS		
DESCRIPTION	DEPTH RECORDS	HORIZ.	CONT.	PRINT	routs	TAPE ROLLS	PUNCHED CARDS	ABSTRACTS/ SOURCE DOCUMENTS
ENVELOPES								
CAHIERS								*
Wiresdrag	2							
BOXES						¥		1
T-SHEET PRINTS	(List)							

T-SHEET PRINTS (List)

SPECIAL REPORTS (List)

# OFFICE PROCESSING ACTIVITIES

The following statistics will be submitted with the cartographer's report on the survey

	AMOUNTS							
PROCESSING ACTIVITY	PRE- VERIFICATION	VERIFICATION	REVIEW		TQTALS			
POSITIONS ON SHEET					64			
POSITIONS CHECKED		10						
POSITIONS REVISED		3						
DEPTH SOUNDINGS REVISED								
DEPTH SOUNDINGS ERRONEOUSLY SPACED								
SIGNALS ERRONEOUSLY PLOTTED OR TRANSFERRED		Elec cont	rol					
		TIME (MA	NHOURS)					
TOPOGRAPHIC DETAILS		3	-					
JUNCTIONS		0		_	. St			
VERIFICATION OF SOUNDINGS FROM GRAPHIC RECORDS		0	_	-				
SPECIAL ADJUSTMENTS		0	. 2	2				
ALL OTHER WORK	2	2/1	10	7				
TOTALS	2	27	2	1				
PRE-VERIFICATION BY		BEGINNING DATE		ENDING				
Johnnie Griffin		Oct.24,74			:.24,74			
VERIFICATION BY		BEGINNING DATE		ENDING				
Michael Johnson		Oct.25,74			:.31,74			
REVIEW BY		BEGINNING DATE		ENDING				
D. J. Romerburg		11-27-	74	12	2-06-74			

lnep 7. B. Pewers 227-75 11 km

\* U.S. G.P.O. 1972-769-562/439 REG.#6

#### REVIEW

# FIELD EXAMINATION NO. 1, 1974 W.D. WIRE-DRAG INVESTIGATION FLORIDA EAST COAST, VICINITY OF JUPITER INLET

- 1. This wire-drag field examination was made in compliance with Project Instructions SP-AMC-1-R/H-73, dated January 15, 1973.
- 2. The purpose of the field examination was to verify or disprove the wreck of the REPUBLIC charted in lat. 27°00.61', long. 80°02.68'. Information was desired by the Coast Guard as a basis for possible discontinuances of the wreck buoy "WK 16."
- 3. The results of the investigation are shown on the accompanying Mylar overlay inserted in the Descriptive Report.
- 4. This wreck was previously investigated on FE 5 (1944) and falls within the area of survey H-8955 (1967).

The present wire-drag hung at 34 feet on a metal bar reported by divers to protrude 1 foot above the bottom. The position on the present examination is 320 meters westward of the position of the wreck found on FE 5 (1944). The present survey clearance over the prior position of the wreck is only 28 feet, which is 3 feet less than the prior cleared depth and should not supersede it. The present wire-drag is not considered to have effectively covered the prior position of the wreck.

Soundings on survey H-8955 (1967) do not conflict with the effective drag depths of the present field examination. A shoal with a least depth of 35 feet falls in the immediate vicinity of this examination.

5. The cleared depth of 31 feet charted on chart 1247, 5th Ed., dated April 15, 1972, in lat. 27°00.61', long. 80°02.68' from FE 5 (1944) should be retained on the chart. However, it is charted slightly out of position and should be revised in accordance with the position shown on the field examination.

The hang of 34 feet in lat. 27°00.67', long. 80°02.8' on the present field examination is of minor significance as a feature and the cleared depth should be disregarded for charting.


- 6. In smooth plotting this field examination minor errors in the effective drag depths on strip 1 of A day between position 2 and 4 and on the associated A and D sheet were found during review. These errors were not considered significant and do not warrant revisions.
- 7. The Descriptive Report adequately covers all matters pertinent to this examination. No further discussion is considered necessary.


Reviewed by: D. J. Romesburg


December 6, 1974

Inspected by: F. B. Powers

February 27, 1975







#### RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. F.E. No. 1-1974 W.D.

#### INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.

2. In "Remarks" column cross out words that do not apply.

3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
		*	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			-
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Distring 10.
			Full Part Before After Verification Review Inspection Signed Via
	`		Drawing No.
-:		,	Diawing ivo.
			Full Date Defend Africa Visition in Design In the Control of the C
		1	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.

FORM C&GS-8352 SUPERSEDES ALL EDITIONS OF FORM C&GS-975.

USCOMM-DC 8558-P63